

54 31 055

Removing and installing / replacing gas spring strut on convertible top (Z3 Roadster, M Roadster)

Removing and installing rear left lower section of side trim, refer to 51 43 015

Pry out gas spring strut at top with special tool 00 9 319.





Pry out gas spring strut (1) at bottom with special tool 00 9 319 and remove from the vehicle.